

Potential Hazards	Preventative Measures
<p>1. Collapse of excavation</p> <p>2. Physical injury due to proximity of plant</p>	<ul style="list-style-type: none"> - Only approved mechanical shovels are to be used to carry out this work. - Plant used to backfill excavations will carry current certification and will be maintained in a safe condition. - The plant will be operated by trained and authorized personnel. - Banks man will be used to control the backfilling operation in order to prevent plant working too close to the excavation edge. - Unauthorized personnel will be excluded from areas where the backfilling of excavation is taking place. - a survey of the area will be carried out to assess risks to any adjacent structures and/or utilities that may exist. - Operators will be briefed on any identified potential hazards.

JSA Backfill Check Point

